




Sign Installation

Guard Rail
Lighting
Signals
ITS

Lyle Landstrom
Fargo District

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SNH-S-NHLJ-6-002(097)317	110	32



This document was originally issued and sealed by Jon E. Markusen Registration Number PE-5453, on 08/05/10 and the original document is stored at the North Dakota Department of Transportation

**US HIGHWAY 2
SIGNING & WETLAND LAYOUT**

Sta/ RP	Sign No.	Assembly No.	Flat Sheet For Signs		Sign Support Length				Support Size	Max Post Len LF	Sleeve Length				Sleeve Size	Anchor EA	Anchor LF	Anchor Size	Reset Sign Panel EA	Reset Sign Support EA	Break-Away EA	Comments
			3A SF	2 SF	1st LF	2nd LF	3rd LF	4th LF			1st LF	2nd LF	3rd LF	4th LF								
503+45 Lt	SA 1E		13.0		5.6				2 x 2 12 ga	12.0					1	4	2.25 x 2.25 12 ga					
503+47 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
507+46 Lt		437	8.4		10.1				2.25 x 2.25 12 ga	10.5					1	4	2.5 x 2.5 12 ga					
555+79 Lt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
556+04 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
556+27 Lt	SA 1E		13.0		5.6				2 x 2 12 ga	12.0					1	4	2.25 x 2.25 12 ga					
608+74 Lt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
609+55 Lt	SA 1E		13.0		5.6				2 x 2 12 ga	12.0					1	4	2.25 x 2.25 12 ga					
609+72 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
633+59 Lt		27	3.0		6.7				2 x 2 12 ga	13.2					1	4	2.25 x 2.25 12 ga					
634+15 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
637+00 Rt	SA D				15.2				2.5 x 2.5 10 ga	20.7	2.5			2.19 x 2.19 10 ga	1	4	3 x 3 7 ga				1	
663+38 Lt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
663+89 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
663+96 Lt	SA 1E		13.0		5.6				2 x 2 12 ga	12.0					1	4	2.25 x 2.25 12 ga					
668+77 Rt			59.5		12.3	12.9	13.4		2.5 x 2.5 10 ga	14.0	2.8	3.4	3.9	2.19 x 2.19 10 ga	3	4	3 x 3 7 ga				3	
704+30 Rt		391	6.2		8.8				2 x 2 12 ga	9.9					1	4	2.25 x 2.25 12 ga					
706+30 Lt		11	12.0		8.4				2.5 x 2.5 10 ga	10.2					1	4	3 x 3 7 ga				1	
706+30 Lt mdn		11	12.0		8.4				2.5 x 2.5 10 ga	10.2					1	4	3 x 3 7 ga				1	
708+31 Rt	SS 27		45.0		9.0	9.8	10.6		2.5 x 2.5 12 ga	11.3	2.0	2.8	3.6	2.25 x 2.25 12 ga	3	4	3 x 3 7 ga				3	
710+38 Lt	SS 28		33.3		8.2	9.0	9.7		2.5 x 2.5 10 ga	10.3					3	4	3 x 3 7 ga				3	
712+36 Rt		405	12.4		8.6				2.5 x 2.5 10 ga	9.8					1	4	3 x 3 7 ga				1	
714+50 Lt		371	6.0		8.6				2 x 2 12 ga	10.0					1	4	2.25 x 2.25 12 ga					
715+37 Rt		16	9.0		8.4				2.5 x 2.5 12 ga	10.5					1	4	3 x 3 7 ga					
715+37 Rt mdn		16	9.0		8.4				2.5 x 2.5 12 ga	10.5					1	4	3 x 3 7 ga					
716+17 Rt		405	12.4		8.6				2.5 x 2.5 10 ga	9.8					1	4	3 x 3 7 ga				1	
716+31 Lt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
716+93 Lt	SA 1E		13.0		5.6				2 x 2 12 ga	12.0					1	4	2.25 x 2.25 12 ga					
717+02 Rt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	
717+15 Lt		405	12.4		8.6				2.5 x 2.5 10 ga	9.8					1	4	3 x 3 7 ga				1	
718+17 Lt		16	9.0		8.4				2.5 x 2.5 12 ga	10.5					1	4	3 x 3 7 ga					
718+17 Lt mdn		16	9.0		8.4				2.5 x 2.5 12 ga	10.5					1	4	3 x 3 7 ga					
719+00 Rt		371	6.0		8.6				2 x 2 12 ga	10.0					1	4	2.25 x 2.25 12 ga					
719+87 Rt	SS 30		25.5		7.7	9.0			2.25 x 2.25 12 ga	9.8	1.7	3.0		2 x 2 12 ga	2	4	3 x 3 7 ga				2	
720+89 Lt		405	12.4		8.6				2.5 x 2.5 10 ga	9.8					1	4	3 x 3 7 ga				1	
721+61 Lt		449	14.2		10.2				2.5 x 2.5 10 ga	12.1					1	4	3 x 3 7 ga				1	

Basis of Estimate
Sign Support Lengths

The sign support lengths have been calculated using the following vertical clearances:





Urban/rural expressway and freeway - 84" (Offset - 60")
Rural Roadway - 60"

This document was originally issued and sealed by Jon E. Markusen, Registration Number 5453, on 8/5/2010 and the original document is stored at the North Dakota Department of Transportation



Sign Summary
Perforated Tube

SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS-DIVIDED HIGHWAY CONTROL SIGNS

D-754-77



ASSEMBLY NO. 446 & 450




- NOTES:
1. See standard D-754-24 for mounting details.
 2. The minimum sign backing material thickness shall be 0.100 inch.
 3. Perforated square tube stringer shall be 1 1/2" x 1 1/2".
 4. All holes shall be punched round for 3/8" bolt.
 5. Assembly:
Single Sign: 445 and 446
One Way Back To Back: 449 and 450

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
15-2-88	
REVISIONS	
DATE	CHANGE
05-01-92	General revisions
06-25-03	Layout revision
10-13-04	Note revisions
12-01-04	PE Stamp added
07-21-07	Revised assembly 445 and 449


This document was originally issued and sealed by
MARK S GAYDOS
 Registration Number
PE-4818,
 on 07/31/07 and the original document is stored at the North Dakota Department of Transportation

BREAK-AWAY COUPLER SYSTEM FOR PERFORATED TUBES



B - The 2 1/2" 12 gauge posts do not need breakaway bases when placed in standard soils. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.

Number of Posts	Telescoping Perforated Tube					
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size In.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			B	2 1/2
1	2 1/2	10			Yes	2 1/2
1	2 1/4	12	2	12	Yes	2 1/4 & 2 Sleeve
1	2 1/2	12	2 1/4	12	Yes	2 1/2 & 2 1/4 Sleeve
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/4	12			Yes	2 1/2
2	2 1/2	10			Yes	2 1/2
2	2 1/4	12	2	12	Yes	2 1/4 & 2 Sleeve
2	2 1/2	12	2 1/4	12	Yes	2 1/2 & 2 1/4 Sleeve
3 & 4	2 1/2	12			Yes	2 1/2
3 & 4	2 1/2	10			Yes	2 1/2
3 & 4	2 1/2	12	2 1/4	12	Yes	2 1/2 & 2 1/4 Sleeve
3 & 4	2 1/4	12	2	12	Yes	2 1/4 & 2 Sleeve
3 & 4	2 1/2	10	2 1/4	10	Yes	2 1/2 & 2 1/4 Sleeve



**BASE PLATE WITH
BREAKAWAY COUPLER**

Telescoping Perforated Tubes						
Tube Size In.	Wall Thickness In.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. ⁴	Cross Section In. ²	Section Modulus In. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.581	0.895	0.499
2 1/2 x 2 1/2	0.135	10	3.432	0.805	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.843
2 1/2 x 2 1/2	0.135	10	4.008	0.979	1.010	0.785

The 2 1/4" size 10 gauge is shown as 2.10" size on the plans. The 2 1/2" size 10 gauge is shown as 2.51" size on the plans.

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SNH-S-NHU-6-002(097)317	110	128

NOTER:

- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.
- Anchor unit shall be the same size as the post and shall have the same specification as the post.
- When used in concrete sidewalk, anchor shall be the same except the anchor plate shall be omitted.
- Four post align shall have over 8" between the first and fourth post.
- In lieu of the breakaway base system on standard D-754-24 the breakaway coupling system may be used. The breakaway coupler system shall be manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements as specified by DIRT BREAKAWAY IND., INC. which meets the test requirements of NCHRP Report 350.
- Base plates and formed plates shall be fabricated from steel meeting the requirements of AASHTO M-183 and M232.

This document was originally issued and sealed by
Jon E. Markusen
Registration Number
PE-5453,
on 08/05/10 and the original document is stored at the
North Dakota Department
of Transportation

**US HIGHWAY 2
PERFORATED TUBE DETAILS
BREAK-AWAY COUPLER SYSTEM**









**How could this have
been prevented ?**

Prior to Construction
Field Review
PS&E Meeting


During Construction
Designer Input
Inspection




Mounting Details Perforated Tube




STRINGER MOUNTING
(WITH STRINGER IN FRONT OF POST)




STREET NAME SIGNS
AND ONE WAY SIGNS
SINGLE POST ASSEMBLY
ONE STRINGER OR
BACK TO BACK MOUNTING




ANCHOR UNIT AND
POST ASSEMBLY




STRAP DETAIL



BOLT MOUNTING



BACK TO BACK
MOUNTING



Anchor plate shall be a minimum of 10 gauge material and galvanized same as post (2 post installation)

Properties of Telescoping Perforated Tubes							
Tube Size In.	Wall Thickness U.S. Gauge	Standard U.S. Gauge	Weight Per Foot Lbs.	Moment of Inertia I _x	Cross Sect. area In. ²	Section Modulus S _x In. ³	I _x + I _y In. ⁴
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172	
2 x 2	0.105	12	2.416	0.372	0.590	0.372	
2 1/2 x 2 1/2	0.105	12	2.773	0.661	0.895	0.496	
2 3/4 x 2 3/4	0.135	10	3.432	0.805	0.841	0.590	
2 7/8 x 2 7/8	0.105	12	3.141	0.804	0.803	0.643	
2 3/4 x 2 3/4	0.135	10	4.008	0.979	1.010	0.763	

The 2 3/4" size 10 gauge is shown as 2.18" size on the plans.
The 2 1/2" size is shown as 2.51" size on the plans.

Note:

- Horizontal stringers - In lieu of perforated tubes, the contractor may substitute z bar stringers. The z bar stringers shall be 1 1/2" x 3/4" thick, 1.08 lbs./ft aluminum or 3.16 lbs./ft steel.
- Metal washers used on sign face shall have a minimum outside diameter of 3/4" ± 1/4" and 10 gauge thickness.
- No Parking Signs: All no parking signs with directional arrows shall be placed at a 30 to 45 degree angle with the line of traffic flow. No parking signs required at the above angles may have the support turned to the correct angle. If the no parking sign is placed with another sign that has to be placed at a 90 degree angle with the line of traffic flow, the detailed angle strap should be used to mount the no parking sign. Flat washers and lock washers shall be used with all nylon washers. Material used for the attachment strap shall be included in the price bid for "Flat sheet for signs."
- In lieu of using the bent bolt to attach the post to the stringer, the contractor may choose to punch the sign backing and place the bolt through the sign, the stringer and the post.
- 4" vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.

Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Will Not Slip In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/2	12
1	2 1/2	12			No	2 3/4	12
1	2 3/4	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/2	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/2	12	Yes		7
2	2 1/2	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 3/4	10	Yes		7

(B) - The 2 1/2" 12 gauge posts do not need breakaway bases when placed in standard soils, but require a shim as specified by the manufacturer. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.
(C) - 3" anchor unit
(D) - 2 1/2" x 12 ga x 18" minimum length external sleeves required.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
6-6-09	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/08/09 and the original document is stored at the North Dakota Department of Transportation

EXIT 138

32nd Ave S

1 MILE

NEXT EXIT 8 MILES





Which Base?



**One Directional
Breakaway Base**



**Multi-Directional
Slip Base**

SIZE MATTERS



LOCATION MATTERS



Offset Matters



Condition Matters



ROAD
CLOSED
1/2 MILE



GENERAL RULES

1. Break-Away at 4"
2. No perforated tube on the Interstate.
3. On Interstate, one post = round pipe
4. On Interstate 2 or more posts = W-Shape
5. Gore Signs (Exit Signs) are round pipe.
6. Multi-Directional bases are used where traffic is multi-directional.
7. In general, vertical clearance = 5' for rural locations.
8. In general, vertical clearance = 7' for Interstate & urban.



Keep Sign Shop in the loop.

1. PS & E Meeting.
2. Up to date with changes.

Expect Changes

1. Get feedback from designer

Traffic Signals

Supplemental Specifications 772.03 Tests and Acceptance 10/15/10

TRAFFIC SIGNAL INSPECTION CONTRACTOR PRE-INITIAL CHECKLIST
North Dakota Department of Transportation, Planning
SFN 59867 (Rev. 02-2011)

The Inspection Date: _____ Contractor: _____ Individual Performing Pre-Inspection: _____
Type of Controller: _____ Type of Mast: _____

Contractor Initials	Traffic Signal Cabinet	Comments
	1. Conflict Monitor Test completed and sent to NDDOT Traffic Operations Section	
	2. One copy of cabinet schematic to NDDOT Traffic Operations Section and one copy in cabinet	
	3. One copy of approved shop drawings to NDDOT Traffic Operations Section	
	4. Signal timings in controller are according to plan	
	5. Coordination offsets are correct according to plan and coordination is working properly	
	6. Advanced flashing beacons are working properly and timing is correct according to plan	
	7. Signal colors during start-up and during flash operation are correct	
	8. Video detection is detecting, inputting to the correct phase, covering the correct lanes	
	9. Video detection fiber optic is working to the agency's office	
	10. One copy of detector loop test to NDDOT Traffic Operations Section	
	11. Detector rack is labeled correctly	
	12. Wires in controller cabinet are properly identified according to plan and NDDOT specifications	
	13. Controller cabinet base is caulked	
	14. Conduit openings with conductors duct sealed, spare conduit openings capped	
	15. Fiber optic patch panel box wires labeled	
	16. Fiber optic patch panel box is secured to cabinet	
	17. Interconnect is hooked up and working properly	
	18. Cabinet call buttons work and are inputting to the correct phase	
	19. Contractor has supplied spare equipment to the owner	
	20. Emergency Pre-emption has been tested and is working properly	
	21. Battery backup has been tested and is working	
	22. Phase designation diagram mounted on cabinet door	
	23. Cabinet door operating properly	
	24. Access pad the correct height above grade	

SFN 77777 (Rev. 01-2011) Page 2 of 2

Contractor Initials	TRAFFIC SIGNALS	Comments
	25. Vertical clearance of all signal heads provided to NDDOT Traffic Operations Section	
	26. Dips loops are installed properly and rubber bungs are installed on signal standards	
	27. Paint on signal standards (any scuff marks have been touched up)	
	28. Signal heads are aligned properly and are level	
	29. Visors and lenses are installed and not damaged	
	30. All backplate screws are installed	
	31. Signaling on mast arms is correct	
	32. Rocket screens are installed in every standard base	
	33. Pedestrian pushbuttons work and are installed properly	
	34. Pushbuttons are ADA accessible	
	35. Pedestrian signal heads are aligned properly	
	36. Pedestrian signaling is correct	
	FEED POINT	
	37. Conduit openings with conductors duct sealed, spare conduit openings capped	
	38. Breakers are labeled properly	
	PULL BOXES	
	39. Loop lead-ins labeled in the pullboxes	

When the contractor has completed and certified the Pre-Initial Checklist, the Initial Inspection can be scheduled after 15 days from the date the Pre-Initial Checklist was completed. When all work items addressed at the Initial Inspection have been completed, the Final Inspection can be scheduled from 30-45 days from the date the Initial Inspection work items were completed.

SFN 59867 Traffic Signal Inspection Contractor Pre-Initial Checklist

Given to Contractor during Pre-Con.

TRAFFIC SIGNAL INSPECTION CONTRACTOR PRE-INITIAL CHECKLIST

North Dakota Department of Transportation, Planning
 SFN 59867 (Rev.02-2011)

Pre-Inspection Date	Contractor	Individual Performing Pre-Inspection
Type of Controller		Type of Master

Contractor Initials	Traffic Signal Cabinet		Comments
	1	Conflict Monitor Test completed and sent to NDDOT Traffic Operations Section	
	2	One copy of cabinet schematic to NDDOT Traffic Operations Section and one copy in cabinet	
	3	One copy of approved shop drawings to NDDOT Traffic Operations Section	
	4	Signal timings in controller are according to plan	
	5	Coordination offsets are correct according to plan and coordination is working properly	
	6	Advanced flashing beacons are working properly and timing is correct according to plan	
	7	Signal colors during start-up and during flash operation are correct	
	8	Video detection is detecting, inputting to the correct phase, covering the correct lanes	
	9	Video detection fiber optic is working to the agency's office	
	10	One copy of detector loop test to NDDOT Traffic Operations Section	
	11	Detector rack is labeled correctly	
	12	Wires in controller cabinet are properly identified according to plan and NDDOT specifications	
	13	Controller cabinet base is caulked	
	14	Conduit openings with conductors duct sealed, spare conduit openings capped	
	15	Fiber optic patch panel box wires labeled	
	16	Fiber optic patch panel box is secured to cabinet	
	17	Interconnect is hooked up and working properly	
	18	Cabinet call buttons work and are inputting to the correct phase	
	19	Contractor has supplied spare equipment to the owner	
	20	Emergency Pre-Emption has been tested and is working properly	
	21	Battery backup has been tested and is working	
	22	Phase designation diagram mounted on cabinet door	
	23	Cabinet door operating properly	
	24	Access pad the correct height above grade	

Contractor Initials	TRAFFIC SIGNALS		Comments
	25	Vertical clearance of all signal heads provided to NDDOT Traffic Operations Section	
	26	Drips loops are installed properly and rubber bungs are installed on signal standards	
	27	Paint on signal standards (any scuff marks have been touched up)	
	28	Signal heads are aligned properly and are level	
	29	Visors and lenses are installed and not damaged	
	30	All backplate screws are installed	
	31	Signing on mast arms is correct	
	32	Rodent screens are installed in every standard base	
	33	Pedestrian pushbuttons work and are installed properly	
	34	Pushbuttons are ADA accesible	
	35	Pedestrian signal heads are aligned properly	
	36	Pedestrian signing is correct	
	FEED POINT		
	37	Conduit openings with conductors duct sealed, spare conduit openings capped	
	38	Breakers are labeled properly	
	PULL BOXES		
	39	Loop lead-ins labeled in the pullboxes	

When the contractor has completed and certified the Pre-Initial Checklist, the Initial Inspection can be scheduled after 15 days from the date the Pre-Initial Checklist was completed. When all work items addressed at the Initial Inspection have been completed, the Final Inspection can be scheduled from 30-45 days from the date the Initial Inspection work items were completed.

Inside Cabinet

Cabinet Drawings

Conflict Monitor Test Report

Loop Meg Test Reports

Spare Load Switches


Spare Detectors

Labels !

Detector Rack

Fiber-Optic Panel

Field Wiring







No fiber-optic Patch Panel

Improper # of terminations

No labels






Not the Best

**Transceiver mounted
too close to door.**

**Fiber patch cable
too small of radius.**



Signal Mechanical Problems



Broken Backplates
Missing Visors
Loose Heads
Broken Astrobrackets

Stripped Screws
Loose Cameras
Missing Confirm Lights
Poor/Corroded Splices

Broken Heads






Reinforcement Plates

Required
Plan Note
Supplemental Spec.



Galvanic Corrosion



Anti-Seize is a new requirement

Traffic Signals

1. Use SFN 59867 Traffic Signal Checklist
2. Read Plan Notes & Special Provisions
3. Read the Standard Specifications
4. Understand the Plans
5. Be Prepared for Changes
6. Make sure you understand the Inspection / Acceptance Process:

Initial Inspection after 14 days

Final Inspection 30 days after Initial

Acceptance 14 days after Final Inspection

Guardrail









03/02/2012











FLARED ENERGY ABSORBING TERMINAL FOR STEEL BREAKAWAY SYSTEM

D-764-2C



GENERAL NOTES

1. Wood posts are required with the Flared Energy Absorbing Terminal except post 1 and 2.
2. All bolts, nuts, cable assemblies, cable anchors and bearing plates shall be galvanized.
3. The lower sections of the posts shall not protrude more than 4 inches above the ground (measured along a 60 inch cord). Site grading may be necessary to meet this requirement.
4. Lower post sections shall not be driven with the upper post attached. If the post is placed in a drilled hole, the backfill material must be satisfactory compacted to prevent settlement.
5. When rock is encountered during excavation, a 12" diameter post hole 20" deep may be used (if approved by the Engineer. Granular material will be placed in the bottom of the hole approximately 2 1/2" deep to provide drainage. The soil tubes shall be field cut to length, placed in the hole and back filled with adequately compacted material excavated from the hole).
6. The breakaway cable assembly shall be taut. A locking device (vice grips or channel lock pliers) should be used to prevent cable from twisting when tightening nuts.
7. The wood blockouts shall be "toe nailed" to the rectangular wood posts to prevent them from turning when wood strikes. The nail shall be 20 penny and galvanized.
8. The Flared Energy Absorbing Terminal shall be flared only when the approach guardrail is parallel with the roadway. When the approach guardrail is flared of 16:1 to 10:1, the Flared Energy Absorbing Terminal shall have only the flare rfts of the guardrail. When the guardrail flars is between 10:1 and 7:1, the Flared Energy Absorbing Terminal shall be turned parallel to the roadway.



ITEM #	QTY	BILL OF MATERIALS
F3000	1	IMPACT HEAD
F1303	1	W-BEAM GUARDRAIL END SECTION, 12 GA.
G1203	2	W-BEAM GUARDRAIL, 12 GA.
HP1A	1	FIRST POST ASSEMBLY TOP
HP1B	1	FIRST POST ASSEMBLY BOTTOM
HP2A	1	SECOND POST ASSEMBLY TOP
HP2B	1	SECOND POST ASSEMBLY BOTTOM
P671	5	WOOD CRT POST
P675	5	TIMBER BLOCKOUT OR RECYCLED EQUIV.
E750	1	BEARING PLATE
S760	1	CABLE ANCHOR BOX
E770	1	BCT CABLE ANCHOR ASSEMBLY
S785	1	GROUND STRUT HINGED POST
HARDWARE (ALL DIMENSIONS IN INCHES)		
B140404	2	1/4 Dia. x 4 HEX BOLT
W014	4	1/4 WASHER
N014	2	1/4 HEX NUT
B58012Z	17	3/8 Dia. x 1 1/4 SPLICE BOLT
B581802	4	5/8 Dia. x 10" H.G.R. BOLT (POSTS 3 THRU 6)
B580904A	1	5/8 Dia. x 9" HEX BOLT GR 5
W050	5	5/8 WASHER
N050	22	5/8 Dia. H.G.R. NUT
B340B54A	1	3/4 Dia. x 8 1/2 HEX BOLT GR A449
N030	1	3/4 Dia. HEX NUT
N100	2	1 ANCHOR CABLE HEX NUT
W100	2	1 ANCHOR CABLE WASHER
S858A	8	CABLE ANCHOR BOX SHOULDER BOLT
N055A	8	1/2 A325 STRUCTURAL NUT
W050A	16	1 1/8 OD x 3/8 ID A325 STR. WASHER

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
09-01-08	
REVISIONS	
DATE	CHANGE
12-21-00	Flared energy absorbing terminal note
09-29-01	Added steel breakaway post
04-14-02	Revised steel breakaway post and flared end post
12-03-04	Revised steel breakaway post
09-05-05	Revised posts 1 & 2, rail end plate
04-05-06	Changed CRT post & blockout. D15, T-8 and added T to section B-B
01-04-07	General revisions
08-12-07	Rev. dimension to center of guardrail to 31"

This document was originally issued and sealed by Mark S. Gaydos, Registration Number PE-4518, on 09/12/07 and the original document is stored at the North Dakota Department of Transportation

Guardrail

1. Know what type
2. Know which standard
3. Records to Maintenance.

Feed Points

Common Problems

1. No Labels on Breakers
2. Improper Locks
3. Improper Grading
4. Less than Ideal Location

11/29/2011 12:30:43



11/29/2011 12:27:48



11/29/2011 12:12:53

