

Click on link below for:

[CHANGES TO DESIGN MANUAL](#)

[CHANGES TO DESIGN MANUAL REFERENCE AND FORMS](#)

CHANGES TO DESIGN MANUAL - 2016

Date	Chapter	Section	Description
10/4/2016	1	2	Updated numerous permitting and environmental report items.
9/30/2016	5	5	Exception was added to allow smooth-wall steel Jacked/Bored pipe installations for divided highways with depressed medians.
7/7/2016	2	3	Added internal guidance for posting public meeting advertisements to the NDDOT Calendar.
6/6/2016	5	2	Updated to reference HEC 18 5th Edition (2012) requirements in which the 200-year discharge is now acceptable for use as the scour design check flood frequency. Also added reference to USGS Bulletin 17B.
1/26/2016	1	2	Revised the Utility Coordination and Utility Engineering descriptions.
1/26/2016	3	4	Revised the replacement of approach and centerline culverts for projects. Also, minor revisions to sliver grading and grade raises.
1/26/2016	3	11	All new lighting installations to be LED systems.
1/26/2016	3	14B	Clarified that Design ADT is the total for both directions. Also, updated Table 1 and Table 1 to be consistent with the 2011 AASHTO Roadside Design Guide.
1/26/2016	5	1	Revised to include the most recent 2015 USGS Regression Equations. Also, additional guidance added for determination of Ruggedness Number.
1/26/2016	5	5	Guidance added when to allow Polypropylene Pipe (Type S) as a plastic pipe alternative under paved roadways.
1/26/2016	5	5A	Added backfill height table for Polypropylene Pipe (Type S).

CHANGES TO DESIGN MANUAL - 2015

Date	Chapter	Section	Description
12/2/2015	1	10A	Added Bridge Design Section and M&R Geotech Section.
6/24/2015	N/A	N/A	Updated preliminary engineering distribution list to include FHWA circulation of draft DCE for PODI only.
6/24/2015	1	2	Changed flagging value for railroad flagging and updated Design Right of Way Limits submittals for internal design
6/24/2015	3	1C	Added SP information and RIMS vertical clearance to Final Office Plan Review checklist
5/13/2015	5	1,2,3,4	Sections 1 through 4 and related appendixes have been re-written and completely revised. Many items have changed. <i>(Sections 5 & 6 remain unchanged with no revisions.)</i>
5/13/2015	1	15	Updated to newer version of reference publications for "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals" & "AASHTO LRFD Bridge Design Specifications".
5/6/2015	1	2	Added FHWA to be invited to Management Presentation for PODI projects.
5/6/2015	1	7	Deleted most of this section about plan sheet order, as it is covered in detail within Chapter 6 CADD Manual.
5/6/2015	1	8	Added guidance for displaying consultant company firm name on the title sheet of plans.
5/6/2015	3	3	Revised spiral curve policy to be consistent with AASHTO. Added guidance for Flared Intersections (D-203-7) and Rural Approaches (D-203-8).
5/6/2015	3	11	Deleted the old lighting warrants and reference the new lighting warrants available on NDDOT website.
5/6/2015	3	12	Removed span length table from Standard Drawing D-772-6&7 and added them to this section.
5/6/2015	3	20	Added guidance that SP's must be PE stamped if they contain an engineering related work product.
1/30/2015	1	8	Added descriptions and process for supplemental data with project plans.
1/30/2015	3	5	Added clarification of when to use salvaged base vs. aggregate base course CL 5 with projects.

CHANGES TO DESIGN MANUAL - 2014

Date	Chapter	Section	Description
7/28/2014	2	3	Added descriptions and process for new SOV Letter #8.
7/28/2014	3	3	Revised left turn lane minimum storage lengths. Also added section to provide guidance concerning geometrics of truck acceleration/deceleration lanes at railroad crossings.
7/28/2014	3	10A	Updated the pavement marking goal tables.
5/12/2014	2	4	Added new section, "Wetlands, Vegetation, & Environmental Permitting"
4/16/2014	1	10A	Updated distribution list for FHWA Projects of Division Interest (PODI), which essentially replaced Full Involvement.
4/16/2014	5	5A	Added more description for measurement of cover or pipe
4/16/2014	3	1C	Revised the Final Office Plan Checklist
4/16/2014	3	21	Added sections to describe Alternates, Options, Tied Projects, Sub-Projects, and other minor updates
3/11/2014	5	5	Revised to permit local governing entity to select pipe materials for off state system projects.
3/11/2014	5	5A	Added pipe backfill height tables for 5" x 1" corrugated pipe.
3/11/2014	1	6	Revised to correctly reference 2011 AASHTO Green Book.

CHANGES TO DESIGN MANUAL - 2013

Date	Chapter	Section	Description
12/31/2013	-	-	Added Construction Services – Environmental Review Section to the Distribution Lists.
12/27/2013	3	19A	Added this section for maintaining traffic for work zones.
11/27/2013	1	1, 2	Combined these two sections both into Chapter 1 Section 1.
11/27/2013	1	2	Revised this section to the Milestone Program.
11/27/2013	1	2A	Add this section to contain the Milestone Flowcharts.
11/27/2013	2	1	Revised this section due to new DCE documents and environmental reference updates.
11/27/2013	2	2	Moved the Milestone Program to Chapter 1 Section 2, and revised this section to now be Environmental Documentation to detail new DCE process and other updated environmental information.
11/27/2013	2	2A	Moved the Milestone Flow Charts to Chapter 1 Section 2A. Revised this section to Cultural Resource Procedures Outline
11/27/2013	2	3	Revised this section to now be Public Involvement and Coordination due to new DCE process.
11/27/2013	2	4,5,6,7	Deleted these sections and appendixes.
10/23/2013	3	13B	New section added for guardrail length of need details.
8/21/2013	3	9	The section was updated (last page of section) to now require Type IV and Type XI retro-reflective sheeting.
8/21/2013	3	9A	The signing detail figures were revised to be compliant with 2011 MUTCD.
8/21/2013	3	10B	The marking detail figure has been revised to be consistent with current practice of using message arrows in lieu of "ONLY" pavement marking for turn lanes.
3/28/2013	1	4	The map of the NHS system was updated.
1/31/2013	3	15	This section has been replaced by new section to describe: fills over 7', foreslope flattening, and flattening at culverts.
1/31/2013	3	15A	This section has been deleted.
1/31/2013	3	15B	This section has been deleted.
1/31/2013	3	14	Minor revision guardrail section which added text to be consistent with the <i>DESIGN GUIDELINES</i> .
1/16/2013	1	8	The section was revised to reflect internal submission of electronic and hard copy plans. O: drive, plan holding folder, DIP, etc...
1/16/2013	2	3C	Civil Rights was added to the distribution table to be invited to public meetings.
1/16/2013	3	4	The section was revised to incorporate guidance for sliver grading, borrow, waste, grade raises, and culvert guidance.

CHANGES TO DESIGN MANUAL - 2012

Date	Chapter	Section	Description
12/5/2012	3	3	Updated the turn lane design criteria for length, storage, etc..
12/5/2012	3	14	Updated section to clarify Safety Reviews for Minor Rehab, Structural Improvement, and Major Rehab types of projects.
9/20/2012	2	2	Updated section to incorporate numerous new milestone items.
9/20/2012	2	2A	Replaced section to display flow charts for specific milestone items.
7/23/2012	2	4	Updated public meeting process to include SFN forms for sign in sheets and participation survey. Also revised Local Gov't process.
5/31/2012	1	15	The reference publications were updated. Revised to use the 2011 AASHTO Green Book.
4/10/2012	1	4	The HPCS and NHS maps were updated.
4/10/2012	1	15	The reference publications were updated.
4/9/2012	1	10A	Revised the distribution list for plan reviews.
4/9/2012	2	3C	Revised the distribution list for environmental documents.
2/3/2012	5	5	This section was revised to incorporate the updated revisions to the NDDOT Alternate Pipe Materials Policy.
2/3/2012	5	5A	The backfill tables were revised to clarify where minimum cover is measured from for paved and unpaved roadways.

CHANGES TO DESIGN MANUAL - 2011

Date	Chapter	Section	Description
12/7/2011	N/A	N/A	The Master Table of Contents was updated.
12/7/2011	3	1C	Added new items to the Final Office Plan Review Checklist.
12/7/2011	2	4	Removed requirements for floodplain/wetland info on advertisements for public meetings
7/25/2011	4	All Sections	Chapter IV "Structural Design" was re-written to update Bridge Division policies, procedures, and incorporate the LRFD manual into the Design Manual.
2/1/2011	3	3	Revision to reflect turn lane length table is for non-controlled approaches.
2/1/2011	1	10A	Revised distribution list. Planning Division was taken off list and now only shows Programming Division for plan reviews.
2/1/2011	2	3C	Revised distribution list. Planning and Programming Divisions are now separate Divisions.

CHANGES TO DESIGN MANUAL - 2010

Date	Chapter	Section	Description
11/12/2010	1	15	Updated to reflect the most current reference publications in use by NDDOT, as well as adopted manuals.
11/12/2010	2	2	Added new utility and ETS PCR review milestone items.
11/12/2010	2	3	Revised the attendee requirements for management presentations.
11/12/2010	3	8	Revised this section to be consistent with the "Coordination and Notification for Utility Relocation, Adjustments, and Reimbursement" Policies and Procedures on the website.
10/7/2010	2	5	Revised the ECL description and procedures.
9/22/2010	1	6	Minor Rehabilitation sliver grading methods and descriptions of the <i>DESIGN GUIDELINES</i> have been revised.
9/16/2010	3	11, 12	Revised to add lighting and traffic signal foundation size table
6/17/2010	2	3	Revised the Wetland Delineation and Wetland Jurisdictional Request information.
5/20/2010	2	4	Added information to SOV section that talks about how Local Government Entities such as cities or counties are to fill out SOV Letters #2 and 5.
5/6/2010	2	5	Revised ECL correspondence with ND State Water Commission via SOV Letter #6.
4/20/2010	3	20	Special provision request timelines were revised, including TERO and ITS special provisions.
3/25/2010	3	14B	The backslope rates were revised to be consistent with the AASHTO Roadside Design Guide.
3/25/2010	1	4	Shoulder guidance was added for Interregional highways, maps updated, and the urban maps were removed and included as reference to the NDDOT website.
3/2/2010	3	6	This section had multiple revisions including: rumble strips, approach surfacing policy, and asphalt surfacing descriptions.
2/4/2010	1	6	Preventive Maintenance subcut repair work was added to the <i>DESIGN GUIDELINES</i> .
1/8/2010	1	6	The slough/shoulder treatment methods of the <i>DESIGN GUIDELINES</i> have been revised.

CHANGES TO DESIGN MANUAL - 2009

Date	Chapter	Section	Description
12/31/2009	1	11	The "Plan Addendum Summary and Approval" form was incorporated into this section.
10/30/2009	3	5	This section was revised regarding permeable bases and other items.
10/30/2009	1	7	New plan sections were added, including Section 075 Wetlands, Erosion Control, and Seeding.
9/25/2009	3	2	The section was revised to describe the regulation of work products of Professional Engineers and Surveyors.
9/24/2009	1	6	The <i>DESIGN GUIDELINES</i> were revised regarding Minor Rehab overlays and Sliver Grading.
9/24/2009	4	2	Design Memo 02-2005 was incorporated regarding box culvert length determination.
7/30/2009	2	3	The wetland delineation, jurisdictional request information was updated. The safety review, traffic ops, and pavement information was also updated.
6/17/2009	5	3	This section was revised to be consistent with the Alternative Pipe Selection criteria. Other minor revisions were done.
6/8/2009	3	3	Incorporated the new turn lane dimensions table. Also moved small sub-section on Driveway and Access Management to Section III-16.
6/8/2009	3	13	Moved Driveway and Access Management from III-03 to this section.
6/2/2009	1	8	The Standard Drawing sub-section was updated.
6/2/2009	1	10	The distribution information and descriptions for plan reviews were updated.
6/2/2009	3	1A	The Plan Design and Development Checklist was updated to be consistent with plan standards.
6/2/2009	3	1B	The Plan Review Checklist was updated to be consistent with plan review process.
5/12/2009	1	8A	Updated the Electronic Plan Sheet Submittal Checklist to require test printing of electronic .pdf plans.
5/12/2009	3	4	The procedures for State Optioned Borrow were updated, as well as other multiple minor revisions.
5/12/2009	3	9	The section was updated to require Clearview Highway Font for all Variable Message Signs (Guide Signs).
5/12/2009	3	18	The Salvaged Credit Policy was incorporated into this section.
4/21/2009	2	4	Added SOV letter #6 description.
4/16/2009	2	3C	Added Traffic Ops Section to PCR distribution list.
4/8/2009	2	2	Multiple milestone activities and descriptions were revised.
4/8/2009	2	2A	Multiple Milestone activities and responsible Divisions were revised.
4/8/2009	TOC	TOC	Table of Contents was revised.
2/26/2009	1	11	Updated the electronic submittal and descriptions for plan addendums and change orders.
2/11/2009	2	3C	Updated the preliminary engineering Distribution List Appendix II-03A.

CHANGES TO DESIGN MANUAL – 2009 (Continued)

Date	Chapter	Section	Description
2/11/2009	1	8A	Updated the Electronic Plan Sheet Submittal Checklist Appendix I-08A to distinguish max file size of 40 MB.
2/3/2009	1	6	The <i>DESIGN GUIDELINES</i> were revised to distinguish that design exceptions are not needed for roadway width on Preventive Maintenance projects, except for thin lift overlays projects they are still required.
1/23/2009	1	8	Updated the submittal, distribution, and requirements of final electronic plans.
1/23/2009	2	5	Updated the submittal, distribution, and requirements for the ECL.
1/8/2009	1	6	The <i>DESIGN GUIDELINES</i> were revised to clarify sliver grading for Minor Rehabilitation projects, including additional slough treatment details. Design Exception information was also revised.
1/8/2009	3	10A	Updated the pavement marking life/expectancy table.

CHANGES TO DESIGN MANUAL - 2008

Date	Chapter	Section	Description
12/23/2008	5	5A	15" and 18" pipe sizes were added to the Pipe Culvert Backfill Height Tables on page 6 & 7.
12/23/2008	5	5	The Pipe Material Selection process was revised concerning pipe extensions.
12/17/2008	1	10A	Updated Appendix 1-10A Plan Review Notification, Distribution, and Attendance List regarding PM projects and FHWA involvement
12/16/2008	1	8A	Updated Appendix I-08A Electronic Plan Sheet Submittal Checklist to included D-20 Standard Drawings in the back of the plans.
12/4/2008	5	5A	Created new Appendix V-05A for Pipe Culvert Backfill Height Tables.
12/4/2008	5	5	The Pipe Material Selection process was placed in Section V-05 of the Design Manual.
11/26/2008	1	4	Updated the Design Characteristics to be consistent with the <i>DESIGN GUIDELINES</i> for all highway classifications.
11/14/2008	1	6	Updated the <i>DESIGN GUIDELINES</i> regarding the guardrail and rail system for roadway and bridge projects.
9/29/2008	4	2	Updated Section IV-02.02.07 Pedestrian Facilities, regarding pedestrian requirements for structures.
9/29/2008	4	4	Added Appendix IV-04 I, regarding pedestrian details for structures.
8/20/2008	2	5	Updated Project Concept Report (PCR) environmental documentation including current PCR policy, format, and consistency with PCR Template.
8/20/2008	2	5C	Updated Appendix C Project Concept Report Outline.
8/13/2008	1	8	Updated for Final Plan Submittal Process for hard copy and electronic plans, and Electronic Plan Sheet Submittal Checklist policy.
8/13/2008	1	8A	Added Appendix A for Electronic Plan Sheet Submittal Checklist.
6/16/2008	1	6	The <i>DESIGN GUIDELINES for Preventive Maintenance, Minor Rehabilitation, Structural Improvement, Major Rehabilitation, and New/Reconstruction Projects</i> were incorporated into this section.
6/16/2008	1	4	The State Highway Performance Classification was moved from Section I-06 to Section I-04, which includes the State Highway Performance Classification map and descriptions.
4/22/2008	1	15	Updated Reference Publications list.
2/27/2008	2	4	Updated section concerning Public Involvement.

CHANGES TO DESIGN MANUAL - 2007

Date	Chapter	Section	Description
12/31/2007	3	1C	Added item for projects with painting.
12/17/2007	2	5	Revised App.C from PCR checklist for maintenance to PCR outline
12/17/2007	2	5	Deleted Appendix D, Appendix E and Appendix F
12/10/2007	1	10	Minor update
10/23/2007	3	13	Revised link for Traversable End Sections in Section III-13.05.04
10/12/2007	2	5H	Updated Project Cost History
10/12/2007	2	7	Major update
10/12/2007	3	7	Major update, incorporated material from Design Memo No. 03-2004
10/1/2007	2	3	Minor update
8/24/2007	3	8	Minor update, Revised cost for audit requirement
8/24/2007	3	17	Minor update
8/24/2007	3	18	Minor update
8/24/2007	3	23	Minor update
8/10/2007	1	10	Major update
8/10/2007	2	4	Major update
8/10/2007	3	1	Major update
8/10/2007	3	3	Major update
8/10/2007	3	13	Major update
8/10/2007	3	13A	Major update
8/10/2007	3	14	Major update
8/10/2007	3	14A	Major update
8/10/2007	3	15B	New section added
8/10/2007	3	20	Major update
6/11/2007	3	17	Update
6/11/2007	3	8	Update
5/29/2007	2	3C	Minor Changes
5/26/2007	3	2	Update
5/25/2007	2	2	Added Scoping Report
5/21/2007	1	12A	Posted
5/21/2007	3	1B	Minor update
5/9/2007	3	2	Update
5/4/2007	3	1B	Made Blanks able to be filled electronically
5/2/2007	2	4A	Deleted this Appendix
5/1/2007	2	3A, 3B, 3C	Minor update
5/1/2007	3	1A, 1B, 1C	Developed Appendix A, B, and C Plan Review Checklists
3/31/2007	3	21	Incorporated Design Memo 02-2004 Incidental Items, 0.75% bond for projects over \$1,000,000, and misc.
3/27/2007	2	3A, 3B, 3C	Added Appendix A, B and C
2/3/2007	2	5H	Update
1/31/2007	1	6	Page 22, removed "requires a design exception" for shoulders. See Appendix I-06 C.
1/16/2007	2	4	Update to SOV section
1/11/2007	1	11	Major update

CHANGES TO DESIGN MANUAL - 2006

Date	Chapter	Section	Description
11/7/2006	1	6	Major update
10/25/2006	1	13B	Update
10/24/2006	1	13A	Update
10/23/2006	1	6E	Replaced with new form
10/17/2006	1	13	Added Appendix A and B
9/1/2006	1	10	Plan Reviews

CHANGES TO DESIGN MANUAL REFERENCE AND FORMS

Date	Description
Design Exception Form	
7/31/2015	Updated form to be consistent with Stewardship agreement.
11/7/2012	Modified for to be DOT form. Changed footer.
2/27/2008	Added Minor Rehabilitation to the note at the bottom of the first page.
11/14/2007	Revised threshold for full FHWA involvement from \$3 million to \$5 million.
5/10/2007	Added electronic distribution statement.
3/29/2007	Updated Work Type on first page. Added Basis for Recommendation on last page.
12/7/2006	Corrected typo on page 2, note 4, bride to bridge.
Legal Display Advertisements and Press Releases	
12/3/2015	Updated all Press Releases and also Public Hearing Advertisement.
12/10/2014	Updated the Public Participation Survey and Instructions.
3/11/2013	Updated the Public Participation Survey and Instructions.
12/5/2012	Updated the Instructions for Public Participation Surveys.
11/7/2012	Add link for Stormwater Poster.
7/23/2012	Updated all public meeting advertisements and press releases. Added sign in sheet, participation survey, instructions, and codes.
4/18/2011	Revised the Public Meeting Sign-In Sheet
1/28/2011	Revised the TTY number on all documents.
9/28/2010	Revised the accessible accomodations paragraph for all documents.
8/11/2010	Replaced the TTY number on all Press Releases and Legal Display Advertisements and replaced with 711.
4/17/2009	Added standard NDDOT public meeting Sign-In Sheet
4/17/2009	Updated all advertisements and press releases contact person information
6/19/2007	Minor revisions to instructions for Press Releases and Legal Display Advertisements
3/27/2007	Added Press Releases
2/9/2007	Consultants to use NDDOT TTY number as noted
1/12/2007	Updated all advertisements
Miscellaneous Sheets	
6/24/2015	Updated 3-01C Final Plan Checklist
5/5/2015	Updated Electronic Plan Submittal Checklist with various items.
4/16/2014	Updated 3-01 C Final Plan Checklist
11/27/2013	Moved the Railroad Crossing Review form here from the Design Manual.
9/18/2012	Added new Borrow Site Report excel document.
12/7/2011	Added new items to the Final Office Plan Review Checklist 3-01C.
12/29/2009	Added the Plan Addendum Summary and Approval form.
6/2/2009	City Utility Disposition Letter was revised to make contact person more clear.

Date	Description
NDDOT Environmental Document Covers	
11/12/2014	Added USFS Biological Evaluation document.
11/15/2013	Added Document Cover Color Codes.
7/1/2013	Replaced all PCR templates with new Documented CATEX template, and moved to NEPA Documentation table.
7/1/2013	Added the Environmental Impact Checklist.
Noise Information	
6/24/2015	Added Noise Analysis Template
8/21/2013	Revised Type 1 Project Determination.
11/7/2012	Added Type 1 Project Determination link.
4/10/2012	The 2011 noise policy was updated. The Noise Abatement Criteria Table, Activity Category E, was changed from 52 Leq(h) for interiors to an 72 Leq(h) for exterior locations only.
8/19/2011	Created table to post the NDDOT Noise Policy.
NEPA Documentation	
12/31/2015	Revised ECL. Added PM Subcut, removed Dec. Doc. for ITS items, and other minor edits.
12/3/2015	Section 7 ESA Guidance was updated due to species removed from USFWS list for the Greater Sage Grouse.
9/21/2015	Added FHWA & USFWS Programmatic BA for NLEB.
5/5/2015	DCE Enviro Impact Checklist was expanded for numerous items.
5/5/2015	Section 7 ESA Guidance was updated due to new species listing for NLEB.
1/30/2015	Updated Section 7 ESA Guidance
11/12/2014	Added Northern Long-Eared Bat (NLEB) Guidance
4/16/2014	Revised the ECL. Changed Decision Document items, added airport question, and added Surveillance Camera.
11/27/2013	Revised the ECL. Added additional work items and NDDOT signatures.
7/1/2013	Replaced all PCR templates with new Documented CATEX template, and moved to NEPA Documentation table.
7/1/2013	Added the Environmental Impact Checklist.
5/13/2013	Added/Revised documents for Nationwide Section 4(f) for Bridges, Historic Sites, and Recreation Areas.
12/6/2012	Revised ECL/Decision Document title page to read "INTERIM DIRECTOR Grant Levi, P.E.
12/7/2011	Added the Nationwide Section 4(f) Evaluation for Historic Bridges
4/27/2011	Revised the ECL to show the new cost per mile of a PM Overlay
4/27/2011	Posted the revised Cost History Sheet
10/7/2010	Revised the ECL, Added Worksheet C.
5/6/2010	Revised ECL correspondence with ND State Water Commission via SOV Letter #6.
Solicitation of Views Resources	
7/7/2016	Updated Master SOV.
6/6/2016	Updated Master SOV. Also added Transit and Railroad contacts.
12/31/2015	Updated SOV Letter #2 - USACE.
12/31/2015	Updated Master SOV
12/2/2015	Updated Master SOV
6/24/2015	Updated Master SOV
5/5/2015	Updated Master SOV and Letter #7
7/24/2014	Added new SOV Letter #8. Also revised contact person for letters 1,3,4,6,7
4/16/2014	Revised Letter #2 US Corps of Engineers

Date	Description
Utility Coordination	
12/31/2015	Added new forms for Utility Coordination and Utility Engineering.
11/16/2010	Added various utility coordination templates/letters.
Environmental Information	
9/21/2015	Added Appendix F5 and Appendix F6.
7/31/2015	Updated Appendix A5
1/30/2015	Updated Appendix A5, D1, D2, D4
11/12/2014	Updated Appendix A3
7/8/2014	Updated Appendix A1, A3, A4, A5, F1, F2
5/12/2014	Added numerous links for templates/forms that are referenced in the appendix of Chapter 2 Section 4 of the Design Manual.
4/16/2014	Revised Section 7 ESA Guidance.
3/11/2014	Updated Wetland Tables and Wetland Info and 404 Permit Guidance for Consultants
12/27/2013	Added new documents for Floodway Authorization Guidance, Sovereign Lands Permit, and USFWA General Special Use Permit.
12/27/2013	Revised Floodplain Permit Guidance and Wetland Information Guidance.
8/21/2013	Revised Section 7 ESA Guidance.
2/14/2013	Added new link for the Floodplain Permit Application Form
2/14/2013	Added new link for the Regional Service Area-RSA
2/14/2013	Revised the Wetland Tables and the Wetland and Deep Water Impacts Example
2/14/2013	Revised the Wetland Information Guidance for both NDDOT and consultants
11/7/2012	Updated Additional Info for Wetland JR. Deleted Instructions, now on Info link.
9/17/2012	Updated the Wetland Tables.
4/10/2012	Added example typical section for wetland and deep water impacts.
11/4/2010	Added links for Floodplain, Permit, and Wetland Guidance for Consultants and NDDOT Designers.
5/6/2010	Added links for Example Wetland Delineation Reports, for both Field and Office delineations
5/6/2010	Updated the Wetland Tables.
7/29/2009	Additional Information for Wetland Jurisdictional Requests, with Instructions was added.
6/2/2009	Wetland Tables were updated for office/field delineations, and for environmental documentation and permitting purposes.
Safety Reviews	
3/11/2014	Minor typos and edits to Safety Review Templates for MaR, MaR widening, & SI
12/4/2012	Added new "Safety Reviews" area with links for safety review templates and spreadsheets.