RESEARCH REPORT DOCUMENTATION PAGE

1. Report No. ND 97-02	Report Date March 2011	3. Contract No. N/A		4. Project No. IM-6-029(027)161
5. Title and Subtitle	Maich 2011	IN/A	6. Report Type	7. Project No.
Evaluation of an Experimental Portland Cement Concrete Pavement Project			Click on link to open report Work Plan ☐ Construction☐ Evaluation ☐ Final ⊠	8. Project No. 9. Project No. 10. Project No.
11. Author(s)/Principle Investigator(s)				
Curt Dunn, Tom Bold, Bryon Fuchs, John Wolf, Rebecca Espinoza, and Andy Mastel 12. Performing Organization Name and Address 13. Sponsoring Agency Name and Address				
NDDOT M+R North Dakota DOT NDDOT OTHER* Materials and Research Division NDSU 300 Airport Road UND Bismarck ND 58504-6005 UGPTI OTHER* *see supplementary notes		North Dakota DOT Materials and Research Division 300 Airport Road Bismarck ND 58504-6005		
14. Supplementary Notes				
15. Abstract				
Purpose and Need				
Concrete pavement has been utilized in every state due to its durability. However, the pavements constructed in the last 10 to 20 years appear to be less durable than those constructed previously. The only properties normally targeted are strength and air content. These two factors alone can not guarantee durability in PCC pavement. The properties currently targeted are found using what is known as a "recipe". There is need to change the design philosophy and look at other properties besides strength and air.				
<u>Objective</u>				
The objective is to move toward an end result specification for concrete paving by moving away from recipe mixes to a mix design philosophy with target properties.				
<u>Scope</u>				
The scope was to construct an experimental recycled portland cement concrete pavement. The experimental pavement was broken up into test sections with each having different design parameters. Individual items to be evaluated over the long term are as follows: Distresses in the pavement, overall pavement condition, ride, and long term compressive strength. The project will be evaluated for a period of ten-years with reports every two years. The location of the project is on Interstate 29 in the southbound lane from reference point 163 to 175. This section of the roadway is located approximately 22 miles north of Grand Forks, ND.				
Summary				
Results of the final evaluation indicate that all sections are performing well. Minor distresses are noted in all test sections. Ride characteristics remain very good. Sections containing water reducing admixtures seem to be performing slightly better than those without admixtures.				
16. Key Words	17. Distribution Statement No restrictions. This	document is availab	le to the public by clicking this	18. No. of Pages 58
Pavement Concretes	link.: <u>Report</u>	acountert to availar	io to the public by ellering tills	
Aggregates Admixtures	North Dal	cota Department c	f Transportation	19. File type/Size
Design	Materials and Research Division:		PDF/3.7 MB	
Composite	300 Airport Road Bismarck ND 58504-6005			
	Office: (701) 32		Fax: (701) 328-0310	