

ND DEPARTMENT OF TRANSPORTATION					SHEET NO. 1 OF 2		ABSTRACT OF BIDS RECEIVED				
PROJECT NO. BRJ-0019(020)				NO. 22434		BIDDER ENGINEERS ESTIMATE		BIDDER MIDWEST CONTRACTING LLC		BIDDER CENTRAL SPECIALTIES INC	
COUNTY & DATE GRANT (037) SEP 08, 2023 09:30AM								MARSHALL, MN		ALEXANDRIA, MN	
LENGTH & TYPE 0.047 10 MI E AND 8 MI N OF CARSON											
COMPLETION TIME 08/03/24 STRUCTURE REPLACEMENT, MINOR GRADING,						C.C. CHECK RANK 00		C.C. BOND RANK 01		C.C. BOND RANK 02	
SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT
103	CONTRACT BOND	L SUM	1.000	3200000	3200000	4000000	4000000	4500000	4500000	4500000	4500000
201	CLEARING & GRUBBING	L SUM	1.000	2700000	2700000	1500000	1500000	2500000	2500000	2500000	2500000
202	REMOVAL OF STRUCTURE	L SUM	1.000	1500000	1500000	1500000	1500000	1500000	1500000	1500000	1500000
203	COMMON EXCAVATION-TYPE B	CY	105000	33000	3465000	20000	2100000	25000	2625000	25000	2625000
203	TOPSOIL	CY	121000	33000	3993000	20000	2420000	20000	2420000	20000	2420000
203	TOPSOIL-WETLAND	CY	93000	43000	3999000	25000	2325000	30000	2790000	30000	2790000
203	BORROW-EXCAVATION	CY	507000	52000	26364000	35000	17745000	73000	37011000	73000	37011000
210	CLASS 2 EXCAVATION-BOX CULVERT	EA	1.000	20000000	20000000	15000000	15000000	10000000	10000000	10000000	10000000
210	FOUNDATION FILL	CY	373000	120000	44760000	110000	41030000	97000	36181000	97000	36181000
210	FOUNDATION PREPARATION-BOX CULVERT	EA	1.000	200000000	200000000	150000000	150000000	50000000	50000000	50000000	50000000
216	WATER	M GAL	11.000	50000	550000	30000	330000	75000	825000	75000	825000
251	SEEDING CLASS II	ACRE	2.000	55000000	110000000	45000000	90000000	80000000	160000000	80000000	160000000
251	WETLAND SEED	ACRE	2.000	42000000	84000000	45000000	90000000	28000000	56000000	28000000	56000000
251	TEMPORARY COVER CROP	ACRE	2.000	20000000	40000000	20000000	40000000	80000000	160000000	80000000	160000000
253	STRAW MULCH	ACRE	4.000	20000000	80000000	28000000	112000000	150000000	600000000	150000000	600000000
256	RIPRAP GRADE II	CY	76000	152000	11552000	132000	10032000	205000	15580000	205000	15580000
260	SILT FENCE SUPPORTED	LF	60000	5500	330000	5000	300000	5000	300000	5000	300000
260	REMOVE SILT FENCE SUPPORTED	LF	60000	1250	75000	500	30000	1000	60000	1000	60000
261	FIBER ROLLS 12IN	LF	700000	3500	2450000	3000	2100000	4000	2800000	4000	2800000
261	REMOVE FIBER ROLLS 12IN	LF	510000	1000	510000	500	255000	1000	510000	1000	510000
302	AGGREGATE SURFACE COURSE CL 13	TON	191000	61000	11651000	58000	11078000	95000	18145000	95000	18145000
606	14FT X 7FT PRECAST RCB CULVERT	LF	54000	22000000	1188000000	27000000	1458000000	29000000	1566000000	29000000	1566000000
606	14FT X 7FT PRECAST RCB END SECTION	EA	2.000	375000000	750000000	370000000	740000000	400000000	800000000	400000000	800000000
702	MOBILIZATION	L SUM	1.000	430000000	430000000	470000000	470000000	450000000	450000000	450000000	450000000
704	TRAFFIC CONTROL SIGNS	UNIT	477000	1800	858600	2000	954000	2500	1192500	2500	1192500
704	TYPE III BARRICADE	EA	12000	215000	2580000	125000	1500000	90000	1080000	90000	1080000
709	GEOSYNTHETIC MATERIAL TYPE G	SY	179000	6500	1163500	5000	895000	5000	895000	5000	895000
709	GEOSYNTHETIC MATERIAL TYPE RR	SY	114000	7500	855000	5000	570000	10000	1140000	10000	1140000
709	GEOSYNTHETIC MATERIAL TYPE S1	SY	179000	6500	1163500	5000	895000	10000	1790000	10000	1790000
754	FLAT SHEET FOR SIGNS-TYPE XI REFL SHEETING	SF	22600	37000	836200	25000	565000	21400	483640	21400	483640
754	STEEL GALV POSTS-TELESCOPING PERFORATED TUBE	LF	64800	22500	1458000	23000	1490400	21000	1360800	21000	1360800
754	OBJECT MARKERS - TYPE III	EA	4000	191000	764000	200000	800000	150000	600000	150000	600000
900	TEMPORARY STREAM DIVERSION	EA	1.000	100000000	100000000	20000000	20000000	20000000	20000000	20000000	20000000
TOTAL					43021780		41967440		46786894		
							NO LIMIT		NO LIMIT		
ACTION TAKEN BY DEPARTMENT OF TRANSPORTATION				AWARD TO: MIDWEST CONTRACTING LLC				WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.			
Deputy Director For Engineering:											
1				DATE OF AWARD				DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering			

ND DEPARTMENT OF TRANSPORTATION				SHEET NO. 2 OF 2		ABSTRACT OF BIDS RECEIVED					
PROJECT NO. BRJ-0019(020)				NO. 22434		BIDDER GLADEN CONSTRUCTION INC		BIDDER EDWARD H SCHWARTZ CO NSTRUCTION INC		BIDDER	
COUNTY & DATE GRANT (037) SEP 08, 2023 09:30AM						LAPORTE, MN		NEW ENGLAND, ND			
LENGTH & TYPE 0.047 10 MI E AND 8 MI N OF CARSON						C.C. BOND RANK 03		C.C. BOND RANK 04		C.C.	
COMPLETION TIME 08/03/24 STRUCTURE REPLACEMENT, MINOR GRADING,											
SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT
103	CONTRACT BOND	L SUM	1000	5000000	5000000	3586000	3586000				
201	CLEARING & GRUBBING	L SUM	1000	3500000	3500000	666670	666670				
202	REMOVAL OF STRUCTURE	L SUM	1000	1400000	1400000	2752000	2752000				
203	COMMON EXCAVATION-TYPE B	CY	105000	32000	336000	75170	789285				
203	TOPSOIL	CY	121000	25000	302500	41430	501303				
203	TOPSOIL-WETLAND	CY	93000	48000	446400	128460	1194678				
203	BORROW-EXCAVATION	CY	507000	21000	1064700	62870	3187509				
210	CLASS 2 EXCAVATION-BOX CULVERT	EA	1000	1450000	1450000	5548000	5548000				
210	FOUNDATION FILL	CY	373000	115000	4289500	128330	4786709				
210	FOUNDATION PREPARATION-BOX CULVERT	EA	1000	1000000	1000000	13333330	13333330				
216	WATER	M GAL	11000	10000	110000	40000	44000				
251	SEEDING CLASS II	ACRE	200	5500000	1100000	1066670	21333				
251	WETLAND SEED	ACRE	200	4500000	900000	3733330	74667				
251	TEMPORARY COVER CROP	ACRE	200	2500000	500000	1066670	21333				
253	STRAW MULCH	ACRE	400	4000000	1600000	2000000	800000				
256	RIPRAP GRADE II	CY	76000	150000	1140000	166670	1266692				
260	SILT FENCE SUPPORTED	LF	60000	9000	540000	6670	40020				
260	REMOVE SILT FENCE SUPPORTED	LF	60000	2000	120000	1330	7980				
261	FIBER ROLLS 12IN	LF	700000	5250	367500	5330	373100				
261	REMOVE FIBER ROLLS 12IN	LF	510000	1000	510000	1330	67830				
302	AGGREGATE SURFACE COURSE CL 13	TON	191000	66000	1260600	75590	1443769				
606	14FT X 7FT PRECAST RCB CULVERT	LF	54000	2800000	15120000	2964700	16009380				
606	14FT X 7FT PRECAST RCB END SECTION	EA	2000	3200000	6400000	45185330	9037066				
702	MOBILIZATION	L SUM	1000	9800000	9800000	127498000	127498000				
704	TRAFFIC CONTROL SIGNS	UNIT	477000	2500	1192500	2000	95400				
704	TYPE III BARRICADE	EA	12000	90000	1080000	166670	200004				
709	GEOSYNTHETIC MATERIAL TYPE G	SY	179000	6500	1163500	5330	95407				
709	GEOSYNTHETIC MATERIAL TYPE RR	SY	114000	7000	798000	5330	60762				
709	GEOSYNTHETIC MATERIAL TYPE S1	SY	179000	6500	1163500	5330	95407				
754	FLAT SHEET FOR SIGNS-TYPE XI REFL SHEETING	SF	22600	21500	485900	32000	72320				
754	STEEL GALV POSTS-TELESCOPING PERFORATED TUBE	LF	64800	21000	1360800	29330	190058				
754	OBJECT MARKERS - TYPE III	EA	4000	150000	600000	260000	104000				
900	TEMPORARY STREAM DIVERSION	EA	1000	8500000	8500000	13333330	13333330				
TOTAL					47399620		64001745				
					NO LIMIT		NO LIMIT				
ACTION TAKEN BY DEPARTMENT OF TRANSPORTATION				AWARD TO: MIDWEST CONTRACTING LLC				WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.			
Deputy Director For Engineering:											
2				DATE OF AWARD				DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering			

ND DEPARTMENT OF TRANSPORTATION				SHEET NO 1 OF 4		ABSTRACT OF BIDS RECEIVED				
PROJECT NO. BRC-2920(055)				NO. 23733	BIDDER ENGINEERS ESTIMATE		BIDDER CENTRAL SPECIALTIES INC		BIDDER BARANKO BROTHERS INC	
COUNTY & DATE MERCER (057) SEP 08, 2023 09:30AM							ALEXANDRIA, MN		DICKINSON, ND	
LENGTH & TYPE CMC 2920, 2 MI E & 6 MI S OF HAZEN										
COMPLETION TIME 08/02/24 STRUCTURE REPLACEMENT, GRADING, & INCI					C.C. CHECK RANK 00		C.C. BOND RANK 01		C.C. BOND RANK 02	
SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT	
103	CONTRACT BOND	L SUM	1.000	200000000	20000000	100000000	10000000	5878200	5878200	
202	REMOVE AGGREGATE BASE & SURFACING	TON	240000	45000	10800000	50000	12000000	10550	253200	
202	REMOVAL OF STRUCTURE	EA	1000	500000000	50000000	200000000	20000000	29295890	29295890	
202	REMOVE EXISTING FENCE	LF	600000	3000	1800000	750	450000	1340	80400	
203	TOPSOIL	CY	190000	10000	1900000	20000	3800000	21280	404320	
210	BOX CULVERT EXCAVATION	EA	1000	400000000	40000000	300000000	30000000	30062810	30062810	
210	CHANNEL EXCAVATION	L SUM	1000	400000000	40000000	45000000	4500000	6194060	6194060	
216	WATER	M GAL	50000	25000	1250000	75000	3750000	56180	280900	
251	SEEDING CLASS II	ACRE	850	1100000	935000	2880000	2448000	856000	727600	
251	WETLAND SEED	ACRE	50	1100000	55000	4800000	240000	2996000	149800	
251	TEMPORARY COVER CROP	ACRE	500	200000	100000	225000	112500	856000	428000	
253	STRAW MULCH	ACRE	450	500000	225000	2120000	954000	1605000	722250	
255	ECB TYPE 2	SY	50000	50000	2500000	9200	460000	5350	267500	
260	SILT FENCE UNSUPPORTED	LF	450000	2500	1125000	2950	1327500	5350	240750	
260	REMOVE SILT FENCE UNSUPPORTED	LF	450000	500	225000	600	270000	1070	481500	
261	FIBER ROLLS 12IN	LF	920000	5000	4600000	2950	2714000	4280	3937600	
261	REMOVE FIBER ROLLS 12IN	LF	920000	1000	920000	520	478400	1070	984400	
262	FLOTATION SILT CURTAIN	LF	45000	30000	1350000	24900	1120500	42800	1926000	
262	REMOVE FLOTATION SILT CURTAIN	LF	45000	5000	225000	4400	198000	5350	240750	
302	AGGREGATE SURFACE COURSE CL 13	TON	260000	75000	19500000	60000	15600000	44260	11507600	
702	MOBILIZATION	L SUM	1000	850000000	85000000	800000000	80000000	45132950	45132950	
704	TRAFFIC CONTROL SIGNS	UNIT	152000	5000	760000	3500	532000	3000	456000	
704	TYPE III BARRICADE	EA	8000	100000	800000	150000	1200000	107000	856000	
752	CORNER ASSEMBLY BARBED WIRE-WOOD POST	EA	9000	1000000	9000000	750000	6750000	1016500	9148500	
754	OBJECT MARKERS - TYPE III	EA	4000	200000	800000	275000	1100000	187250	749000	
900	TEMPORARY STREAM DIVERSION	EA	1000	80000000	8000000	250000000	25000000	59775480	59775480	
SUBTOTAL						30187000		22500490		22151759
ALTERNATE A										
203	BORROW-EXCAVATION	CY	2325000	50000	116250000	000	00	000	00	
210	FOUNDATION PREPARATION	EA	1000	150000000	15000000	000	00	000	00	
210	FOUNDATION FILL	TON	1121000	100000	112100000	000	00	000	00	
210	FOUNDATION FILL-TYPE 1	CY	415000	75000	31125000	000	00	000	00	
256	RIPRAP GRADE II	CY	170000	100000	17000000	000	00	000	00	
709	GEOSYNTHETIC MATERIAL TYPE R1	SY	550000	5000	2750000	000	00	000	00	
714	PIPE CONC REINF 108IN CL II	LF	288000	1650000	47520000	000	00	000	00	
714	END SECT-CONC REINF 108IN	EA	8000	120000000	96000000	000	00	000	00	
752	FENCE BARBED WIRE 3 STRAND	LF	751000	15000	11265000	000	00	000	00	
SUBTOTAL						87669000		NO BID		NO BID
ALTERNATE B										
203	BORROW-EXCAVATION	CY	2485000	50000	124250000	50000	124250000	35110	87248350	
210	FOUNDATION FILL	TON	637000	100000	63700000	43000	27391000	65760	41889120	
210	FOUNDATION FILL-TYPE 1	CY	350000	75000	26250000	90000	31500000	94520	33082000	
210	FOUNDATION PREPARATION-BOX CULVERT	EA	1000	120000000	12000000	50000000	5000000	13176950	13176950	
ACTION TAKEN BY DEPARTMENT OF TRANSPORTATION				AWARD TO: CENTRAL SPECIALTIES INC				WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.		
Deputy Director For Engineering:				3						
				DATE OF AWARD				DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering		

ABSTRACT OF BIDS RECEIVED

SHEET NO 2 OF 4

No.	23733
-----	-------

BIDDER ENGINEERS ESTIMATE

BIDDER
CENTRAL SPECIALTIES
INC

BIDDER	BARANKO BROTHERS INC
--------	----------------------

SEP 08, 2023 09:30AM

LENGTH & TYPE	0.0000	CMC 2920, 2 MI E & 6 MI S OF HAZEN
COMPLETION TIME	08/02/24	STRUCTURE REPLACEMENT, GRADING, & INCI

c.c. CHECK	RANK 00
------------	---------

C.C. BOND	RANK 01
-----------	---------

c.c. BOND	RANK 02
-----------	---------

SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT
256	RIPRAP GRADE II	CY	160000	1000000	16000000	175000	28000000	193310	30929600
606	16FT X 8FT PRECAST RCB CULVERT	LF	150000	3000000	45000000	2600000	39000000	2698470	40477050
606	16FT X 8FT PRECAST RCB END SECTION	EA	4000	45000000	18000000	33000000	13200000	33812550	13525020
709	GEOSYNTHETIC MATERIAL TYPE R1	SY	485000	5000	242500	10000	485000	4420	214370
752	FENCE BARBED WIRE 3 STRAND	LF	800000	15000	1200000	4750	380000	5780	462400
SUBTOTAL					88662500		74679100		75311442
TOTAL					117856000		97179590		97463201
						NO LIMIT		NO LIMIT	

AWARD TO: CENTRAL SPECIALTIES INC

WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.

4

DATE OF AWARD

DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering

ND DEPARTMENT OF TRANSPORTATION				SHEET NO. 3 OF 4		ABSTRACT OF BIDS RECEIVED					
PROJECT NO. BRC-2920(055)			NO. 23733		BIDDER MIDWEST CONTRACTING LLC		BIDDER STRATA CORPORATION		BIDDER GLADEN CONSTRUCTION INC		
COUNTY & DATE MERCER (057) SEP 08, 2023 09:30AM					MARSHALL, MN		GRAND FORKS, ND		LAPORTE, MN		
LENGTH & TYPE CMC 2920, 2 MI E & 6 MI S OF HAZEN					C.C. BOND RANK 03		C.C. BOND RANK 04		C.C. BOND RANK 05		
COMPLETION TIME 08/02/24 STRUCTURE REPLACEMENT, GRADING, & INCI											
SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT		
103	CONTRACT BOND	L SUM	1,000	800,000	800,000	800,000	800,000	1,100,000	1,100,000		
202	REMOVE AGGREGATE BASE & SURFACING	TON	240,000	15,000	3,600,000	25,000	6,000,000	21,000	5,040,000		
202	REMOVAL OF STRUCTURE	EA	1,000	220,000	220,000	380,000	380,000	180,000	180,000		
202	REMOVE EXISTING FENCE	LF	600,000	2,000	1,200,000	1,250	750,000	1,500	900,000		
203	TOPSOIL	CY	190,000	10,000	1,900,000	25,000	4,750,000	17,000	3,230,000		
210	BOX CULVERT EXCAVATION	EA	1,000	140,000	140,000	220,000	220,000	145,000	145,000		
210	CHANNEL EXCAVATION	L SUM	1,000	420,000	420,000	800,000	800,000	900,000	900,000		
216	WATER	M GAL	50,000	30,000	1,500,000	50,000	2,500,000	12,000	600,000		
251	SEEDING CLASS II	ACRE	850	300,000	255,000	288,000	244,800	490,000	416,500		
251	WETLAND SEED	ACRE	50	500,000	25,000	480,000	24,000	550,000	27,500		
251	TEMPORARY COVER CROP	ACRE	500	200,000	100,000	225,000	112,500	250,000	125,000		
253	STRAW MULCH	ACRE	450	250,000	112,500	212,000	95,400	400,000	180,000		
255	ECB TYPE 2	SY	50,000	10,000	500,000	9,200	460,000	12,500	625,000		
260	SILT FENCE UNSUPPORTED	LF	450,000	3,000	1,350,000	2,950	1,327,500	4,000	180,000		
260	REMOVE SILT FENCE UNSUPPORTED	LF	450,000	500	225,000	600	270,000	1,000	450,000		
261	FIBER ROLLS 12IN	LF	920,000	3,000	2,760,000	2,950	2,714,000	4,350	400,200		
261	REMOVE FIBER ROLLS 12IN	LF	920,000	500	460,000	520	478,400	1,000	920,000		
262	FLOTATION SILT CURTAIN	LF	45,000	25,000	1,125,000	24,900	1,120,500	18,500	832,500		
262	REMOVE FLOTATION SILT CURTAIN	LF	45,000	4,000	180,000	4,400	198,000	6,000	27,000		
302	AGGREGATE SURFACE COURSE CL 13	TON	260,000	45,000	11,700,000	42,000	10,920,000	82,000	21,320,000		
702	MOBILIZATION	L SUM	1,000	900,000	900,000	1,355,000	1,355,000	1,580,000	1,580,000		
704	TRAFFIC CONTROL SIGNS	UNIT	152,000	3,000	456,000	2,800	425,600	3,000	456,000		
704	TYPE III BARRICADE	EA	8,000	100,000	800,000	100,000	800,000	100,000	800,000		
752	CORNER ASSEMBLY BARBED WIRE-WOOD POST	EA	9,000	100,000	900,000	95,000	855,000	95,000	855,000		
754	OBJECT MARKERS - TYPE III	EA	4,000	175,000	700,000	175,000	700,000	175,000	700,000		
900	TEMPORARY STREAM DIVERSION	EA	1,000	650,000	650,000	520,000	520,000	850,000	850,000		
SUBTOTAL					18618100		30921850		27698550		
ALTERNATE A											
203	BORROW-EXCAVATION	CY	2325,000	0,000	0,000	0,000	0,000	0,000	0,000		
210	FOUNDATION PREPARATION	EA	1,000	0,000	0,000	0,000	0,000	0,000	0,000		
210	FOUNDATION FILL	TON	1121,000	0,000	0,000	0,000	0,000	0,000	0,000		
210	FOUNDATION FILL-TYPE 1	CY	415,000	0,000	0,000	0,000	0,000	0,000	0,000		
256	RIPRAP GRADE II	CY	170,000	0,000	0,000	0,000	0,000	0,000	0,000		
709	GEOSYNTHETIC MATERIAL TYPE R1	SY	550,000	0,000	0,000	0,000	0,000	0,000	0,000		
714	PIPE CONC REINF 108IN CL II	LF	288,000	0,000	0,000	0,000	0,000	0,000	0,000		
714	END SECT-CONC REINF 108IN	EA	8,000	0,000	0,000	0,000	0,000	0,000	0,000		
752	FENCE BARBED WIRE 3 STRAND	LF	751,000	0,000	0,000	0,000	0,000	0,000	0,000		
SUBTOTAL					NO BID		NO BID		NO BID		
ALTERNATE B											
203	BORROW-EXCAVATION	CY	2485,000	20,000	49,700,000	28,000	69,580,000	31,000	77,035,000		
210	FOUNDATION FILL	TON	637,000	85,000	54,145,000	38,000	24,206,000	63,000	40,131,000		
210	FOUNDATION FILL-TYPE 1	CY	350,000	115,000	40,250,000	85,000	29,750,000	178,000	62,300,000		
210	FOUNDATION PREPARATION-BOX CULVERT	EA	1,000	150,000	150,000	220,000	220,000	105,000	105,000		
ACTION TAKEN BY DEPARTMENT OF TRANSPORTATION				AWARD TO: CENTRAL SPECIALTIES INC				WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.			
Deputy Director For Engineering:				5				DATE OF AWARD			
								DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering			

ABSTRACT OF BIDS RECEIVED

NO. 23733

MARSHALL, MN

c.c. BOND	RANK 03
-----------	---------

GRAND FORKS, ND

C.C. BOND	RANK 04
-----------	---------

LAPORTE, MN

c.c. BOND	RANK 05
-----------	---------

COUNTY & DATE **MERCER (057)**
LENGTH & TYPE **0.080**

SEP 08, 2023 09:30AM

COMPLETION TIME 08/02/24 STRUCTURE REPLACEMENT, GRADING, & INCI

SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT	
256	RIPRAP GRADE II	CY	160000	145000	23200000	120000	19200000	150000	24000000	
606	16FT X 8FT PRECAST RCB CULVERT	LF	150000	3600000	54000000	3300000	49500000	3800000	57000000	
606	16FT X 8FT PRECAST RCB END SECTION	EA	4000	48000000	19200000	39000000	15600000	27000000	10800000	
709	GEOSYNTHETIC MATERIAL TYPE R1	SY	485000	5000	2425000	8000	3880000	6250	303125	
752	FENCE BARBED WIRE 3 STRAND	LF	800000	6000	4800000	5400	4320000	5400	4320000	
SUBTOTAL						92152000		82393600		89931725
TOTAL						110770100		113315450		117630275

NO LIMIT

NO LIMIT

NO LIMIT

AWARD TO: CENTRAL SPECIALTIES INC

WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.

ND DEPARTMENT OF TRANSPORTATION				SHEET NO. 1 OF 1		ABSTRACT OF BIDS RECEIVED					
PROJECT NO. H-5-094(166)051				NO. 24055		BIDDER ENGINEERS ESTIMATE		BIDDER INDUSTRIAL BUILDERS INC		BIDDER SWINGEN CONSTRUCTION CO	
COUNTY & DATE STARK (089) SEP 08, 2023 09:30AM								FARGO, ND		GRAND FORKS, ND	
LENGTH & TYPE 0.000											
COMPLETION TIME 10/28/23 PRESTRESSED CONCRETE BEAM REPAIR						C.C. CHECK RANK 00		C.C. BOND RANK 01		C.C. BOND RANK 02	
SPEC. NO.	ITEM DESCRIPTION	UNIT	QUANTITY	BID PRICE	AMOUNT	BID PRICE	AMOUNT	BID PRICE	AMOUNT		
103	CONTRACT BOND	L SUM	1,000	2000000	2000000	1860000	1860000	2000000	2000000		
702	MOBILIZATION	L SUM	1,000	4000000	4000000	4000000	4000000	5700000	5700000		
704	FLAGGING	MHR	320000	43000	1376000	60000	1920000	55000	1760000		
704	TRAFFIC CONTROL SIGNS	UNIT	1592000	2000	318400	2100	334320	2000	318400		
704	LANE CLOSURE-SIGNAL CONTROL/FLAGGING CONTROL	EA	1000	9200000	9200000	8400000	8400000	8000000	8000000		
704	ATTENUATION DEVICE-TYPE B-50	EA	2000	2400000	4800000	2625000	5250000	2700000	5400000		
704	ATTENUATION DEVICE-TYPE B-75	EA	1000	3200000	3200000	4200000	4200000	4200000	4200000		
704	TYPE III BARRICADE	EA	2000	100000	200000	210000	420000	210000	420000		
704	DELINEATOR DRUMS	EA	65000	25000	1625000	27000	1755000	27000	1755000		
704	SEQUENCING ARROW PANEL-TYPE C	EA	1000	900000	900000	2200000	2200000	2700000	2700000		
704	OBLITERATION OF PAVEMENT MARKING	SF	234000	1700	397800	5500	1287000	5500	1287000		
704	STATE FURNISHED MEDIAN BARRIER	LF	700000	30000	2100000	61000	4270000	50100	3507000		
762	SHORT TERM 4IN LINE-TYPE R	LF	7000000	1300	9100000	2100	1470000	2000	1400000		
762	SHORT TERM 24IN LINE-TYPE R	LF	24000	16000	384000	15750	378000	16000	384000		
930	GIRDER PATCHING	L SUM	1,000	6000000	6000000	5100000	5100000	9000000	9000000		
930	GIRDER REPAIR	L SUM	1,000	8000000	8000000	13700000	13700000	15500000	15500000		
TOTAL					24975080		33369320		39800000		
						NO LIMIT		NO LIMIT			

ACTION TAKEN BY DEPARTMENT OF TRANSPORTATION
 Deputy Director For Engineering:

AWARD TO: **INDUSTRIAL BUILDERS INC**

WHEN PRELIMINARY ARRANGEMENTS ARE COMPLETED.

7

DATE OF AWARD

DEPARTMENT OF TRANSPORTATION Deputy Director For Engineering